

**EXCAVATION WORKS BEHIND THE NEW CUSTOM GATE
(NEAR FIRE FIGHTING AREA) AT APM TERMINALS PIPAVAV**

BILL OF QUANTITY

Sr. No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
1	Excavation in all kinds of strata like Soil & Rock for all works with setting out survey, construction of shoring, shuttering, scaffolding and bracing, dewatering, removal of lumps and other deleterious matter, Uprooting of bushes, vegetation, trees and same is to be shifted to the designated area, removal and disposal of excess and surplus excavated material upto designated location with transportation, loading & unloading, laying and levelling, watering, compacting with 10T vibro roller upto 95% Procter density dressing of sides & bottom, backfilling with approved material etc complete including all manpower, equipments, tools & tackles, transportation, safety PPEs. etc complete and as directed by the Engineer In Charge.	cum	3,31,687		
TOTAL AMOUNT (Rs)					-
GST @__%					-
TOTAL AMOUNT (Rs)					-

Note

- Excavation quantity mentioned in above BOQ is tentative and actual quantity will be calculate based on the Pre Excavation and Post Excavation Survey carried by Contractor in presence of Employer.
- There will be no payments for over-excavation material either in the vertical or the horizontal plane unless instructed otherwise by the Engineer.
If the contractor failed to excavate the required depth in particular section/area or if any patches have been left out,
- There will also be no payment for the such whole area/section wherein the contractor has failed to achieve the required level of +3 m CD.
- The measurement of quantity shall be payable based on pre & post excavation survey carried out by Contractor in presence of Employer.